

An aerial photograph showing a restored coulee ecosystem. A winding stream flows through a lush green area, contrasting with the surrounding agricultural fields. A road runs diagonally across the scene, with a white car visible. The background shows a vast, flat landscape under a clear sky.

Elbow and School Section Coulees Ecosystem Restoration

Design, Construction and Monitoring

Montana AWRA Conference
October 11th, 2023

Presented By:
Robert Sain
Tanner Tompkins



Outline

- Project Location
- Ecosystem Restoration objectives
- Design Approach
- Permitting
- Construction
- Monitoring



Broken O Land and Livestock

Broken O Coulees, north-side, tributaries to Sun River lengths and objectives

	Length (miles)	Length within Broken O	Management Objectives	Comments
Elbow Coulee <i>COMPLETED IN 2021, tributary to School Section</i>	11.6	8	Preserve, Enhance, Restore, Reconnect	fish passage barriers removed, irrigation water removed, Ag infrastructure conflicts reduced with 1,080 acres out of grazing rotation; possible regenerative style grazing in the future
School Section Coulee <i>ON-GOING</i>	15	7	Preserve, Enhance, Restore, Reconnect	Irrigation Dam Removed, 2 miles completed, 400 acres to be removed from grazing rotation.
Big Coulee	21	18	Preserve, Enhance, Restore, Reconnect	To be determined
Duck Coulee	8.2	8.2	Preserve, Enhance, Restore	To be determined
Sun River	130	26	Preserve, Enhance, Restore as needed	To be determined

~20% of the Sun River—tail-water


Altered Watershed Hydrology



STREAMS (COULEE'S) BIASECTED
AND AUGMENTED BY CANALS



SUB-SURFACE IRRIGATION
RETURN FLOW



DIRECT IRRIGATION
WASTEWATER



AGRICULTURE
INFRASTRUCTURE
ENCROACHMENT





Pre-existing Conditions

Ecosystem Restoration Objectives

- Removing as many watershed stressors as possible
- Disconnecting canal water from streams
- Re-aligning channels under or around Ag infrastructure
- Enhancing degraded streambanks
- Enhancement in stream fish habitat and spawning riffles
- Implementing cattle exclusion fencing and protecting riparian areas
- Improving real estate aesthetics and fishing



Design Approach





Initial Assessment Streamflow

LOW FLOW ~ 6 CFS
BANKFUL FLOW ~ 23 CFS


Design Riffle Cross-Sections hydraulics check

Mannings vs R/D84

ELEV (ft)	DEPTH (ft)	AREA (sq ft)	WET PER (ft)	WIDTH (ft)	HYD RAD (ft)	MEAN D (ft)	SLOPE (ft/ft)	ROUGH N (ft ^{1/6})	R/D84	VELOCITY (fps)	U/U*	U ² /2g (ft)	DISCHARGE (cfs)	SHEAR (psf)	POWER (lb/s)	POWER/W (lb/ft/s)	FROUDE	TRANSPORT (lb/s)
3965.25	0.1	0.67	6.91	6.86	0.1	0.1	0.012	0.045	0.4	0.78	3.97	0.01	0.52	0.07	0.39	0.06	0.43	0
3965.35	0.2	1.37	7.33	7.22	0.19	0.19	0.012	0.045	0.76	1.2	4.41	0.02	1.64	0.14	1.23	0.17	0.48	0
3965.45	0.3	2.11	7.74	7.58	0.27	0.28	0.012	0.045	1.08	1.51	4.68	0.04	3.19	0.2	2.39	0.32	0.5	0
3965.55	0.4	2.89	8.15	7.95	0.35	0.36	0.012	0.045	1.4	1.8	4.89	0.05	5.19	0.26	3.89	0.49	0.53	0
3965.65	0.5	3.7	8.57	8.31	0.43	0.45	0.012	0.045	1.72	2.06	5.06	0.07	7.63	0.32	5.71	0.69	0.54	0
3965.75	0.6	4.55	8.98	8.67	0.51	0.52	0.012	0.045	2.04	2.31	5.2	0.08	10.51	0.38	7.87	0.91	0.56	0
3965.85	0.7	5.44	9.39	9.03	0.58	0.6	0.012	0.045	2.32	2.52	5.32	0.1	13.69	0.43	10.25	1.14	0.57	0.41
3965.95	0.8	6.36	9.8	9.39	0.65	0.68	0.012	0.045	2.6	2.72	5.42	0.11	17.27	0.49	12.93	1.38	0.58	0
3966.05	0.9	7.31	10.22	9.75	0.72	0.75	0.012	0.045	2.88	2.91	5.51	0.13	21.25	0.54	15.91	1.63	0.59	0
3966.15	1	8.31	10.63	10.11	0.78	0.82	0.012	0.045	3.12	3.07	5.59	0.15	25.48	0.58	19.08	1.89	0.6	0
3966.25	1.1	9.34	11.04	10.48	0.85	0.89	0.012	0.045	3.4	3.25	5.67	0.16	30.33	0.64	22.71	2.17	0.61	0
3966.35	1.2	10.4	11.46	10.84	0.91	0.96	0.012	0.045	3.64	3.4	5.73	0.18	35.34	0.68	26.46	2.44	0.61	2.77

ELEV (ft)	DEPTH (ft)	AREA (sq ft)	WET PER (ft)	WIDTH (ft)	HYD RAD (ft)	MEAN D (ft)	SLOPE (ft/ft)	ROUGH N [U/U*]	R/D84	VELOCITY (fps)	U/U*	U ² /2g (ft)	DISCHARGE (cfs)	SHEAR (psf)	POWER (lb/s)	POWER/W (lb/ft/s)	FROUDE	TRANSPORT (lb/s)
3965.25	0.1	0.67	6.91	6.86	0.1	0.1	0.012	0	0.4	0.11	0.58	0	0.08	0.07	0.06	0.01	0.06	0
3965.35	0.2	1.37	7.33	7.22	0.19	0.19	0.012	0	0.76	0.58	2.16	0.01	0.8	0.14	0.6	0.08	0.24	0
3965.45	0.3	2.11	7.74	7.58	0.27	0.28	0.012	0	1.08	0.98	3.02	0.01	2.06	0.2	1.54	0.2	0.32	0
3965.55	0.4	2.89	8.15	7.95	0.35	0.36	0.012	0	1.4	1.34	3.66	0.03	3.89	0.26	2.91	0.37	0.39	0
3965.65	0.5	3.7	8.57	8.31	0.43	0.45	0.012	0	1.72	1.7	4.16	0.04	6.28	0.32	4.7	0.57	0.45	0
3965.75	0.6	4.55	8.98	8.67	0.51	0.52	0.012	0	2.04	2.03	4.58	0.06	9.26	0.38	6.93	0.8	0.5	0
3965.85	0.7	5.44	9.39	9.03	0.58	0.6	0.012	0	2.32	2.32	4.9	0.08	12.62	0.43	9.45	1.05	0.53	0.41
3965.95	0.8	6.36	9.8	9.39	0.65	0.68	0.012	0	2.6	2.6	5.18	0.1	16.51	0.49	12.36	1.32	0.55	0
3966.05	0.9	7.31	10.22	9.75	0.72	0.75	0.012	0	2.88	2.86	5.43	0.13	20.94	0.54	15.68	1.61	0.58	0
3966.15	1	8.31	10.63	10.11	0.78	0.82	0.012	0	3.12	3.09	5.63	0.15	25.67	0.58	19.22	1.9	0.6	0
3966.25	1.1	9.34	11.04	10.48	0.85	0.89	0.012	0	3.4	3.35	5.84	0.17	31.25	0.64	23.4	2.23	0.62	0
3966.35	1.2	10.4	11.46	10.84	0.91	0.96	0.012	0	3.64	3.56	6.01	0.2	37.04	0.68	27.73	2.56	0.64	2.77


Design Riffle and Pool treatments




- Notes:
1. Install 10 to 15' tall willow or alder trees (or large shrubs) with root mass embedded into the streambank sub-excavation area.
 2. Mix gravel and cobble in and around willow root masses and for bank toe.
 3. Wrap wetland sod with heavy Jute woven matting. Two sod lifts could be needed to reach bankfull bench.
 4. Use stout stakes to hold matting and sod lifts in place.
 5. Use 100% coconut blanket (ECB) along all disturbed areas including on point bars and along bankfull benches.
 6. Willow branch layering to be placed between wrapped sod and the wood and soil matrix.
 7. Seed under the top, tie-in, of soil wrap prior to stout staking.
 8. Install willow stakes at 2 foot off sets below bankfull.
 9. No need for a berm along the top of bank since willow vegetation should have a similar function.



Example of this treatment used along Elbow Coulee, phase 3



WETSOD LIFTS w/ WILLOW EYE-BROW BANK TREATMENT





- Notes:
1. Grade control riffle to consist of alternating rock vanes with 3" plus cobble and spawning gravel added within interstitial spaces.
 2. Rock inverts located in the TINN model and with key thalweg and bankfull vane inverts located in the structures table.
 3. Sub-excavate below riffle surface and fill with 3" plus ranch rock until point of refusal.
 4. Tie vanes into bankfull at least 8" into the floodplain to prevent near term flanking, prior to vegetation establishment.
 5. For streambank edges install either erosion control blanket (100% coconut) or use actual wetland sod leveled out to match TINN surface.


RIFFLE w/ ROCK GRADE CONTROL



EXAMPLE PHOTO OF A GRADE CONTROL RIFFLE INSTALLED FOR SCHOOL SECTION, PHASE 1



LOG VANE (TYPICAL)




Example Log Vane used on Elbow Coulee, Phase 3

- Notes:
1. Important for both the log vane arm and log elbow section to tie into bankfull and that the top of each log is buried under the bankfull bench.
 2. Apex to start within the downstream portion of riffle prior to 'run'.
 3. Vane arm may consist of one or two logs to make the distance. Two logs may help fill the void and provide better fish habitat.
 4. Fit log vane and elbow together at apex using cables, chain-saw notches or by over-lapping.
 5. Fill space up stream and behind vane arm with a footer log and, or rock or sod prior to stapling geo-textile onto the vane arm.
 6. Either use geo-textile over top of the log vane section.
 7. Add 4" inch plus, ranch rock on top of geo-textile so as to create a smooth tie-into bankfull.



Example Photo of this treatment used up stream in School Section, Phase 1

- Notes:
1. Important that the footer log and rootball are installed below the bottom of the deepest part of the pool (thalweg).
 2. The footer log may have a rootwad or not
 3. Rootwad and footer log to be locked together tight with spaces filled with 3" plus ranch rock.
 4. Add some soil, prior to laying down branches/ willows
 5. Branch layering to be placed under wrapped soil or wrapped sod.
 6. Wrapped sod or soil requires heavy jute matt/ coir wrap
 7. Seed under the top, tie-in, of soil wrap prior to stout staking.
 8. Add 0.6 foot-tall, over-land, run-off berm on top of bank.
 9. Install willow stakes at 2 foot off bank.



Permitting

--Federal

404—USACE NWP 27 authorization
(self mitigating)

--State of Montana

401—DEQ Certification

318—FWP

SWPPP—DEQ—over an acre of land dist.


--County

310—Teton County

Elbow Coulee

Three Phased approach

- Restoration/ re-alignment: ~2 miles
- Stream was re-routed under a canal for fish passage
- Irrigation water re-routed of channel
- Fish passable culvert installed
- Preservation/ self-heal: ~6 miles
- 1,080 Acres excluded from grazing



Floweree Canal
bisects coulees


Elbow Coulee Phases		
Broken O	Length (miles)	Completed
PHASE 1	1.6	2017
PHASE 2	2.4	2019
PHASE 3	4	2020
Total (miles)	8	

Elbow Phase I, 3 reaches







Elbow Coulee STA 61+00 As Built Longpro



- CH
- WS
- BKF
- LIDAR
- P2
- P3
- P4

Elbow Phase 2






Pre-existing Conditions Change to phase 2

- ½ mile downstream of canal crossing
- Irrigation split backwater
- Over-widened channel
- Highly eroded streambanks
- Lacking fish habitat






-3D VIEW TINN Elbow Phase 2, new-alignment

-Channel was cut through established wetland


-Cut material used to plug and convert old channel and canal lateral to emergent wetlands.

2018 aerial/ 2023 photo

REMOVAL OF IRRIGATION WATER, NEW SPILLWAY



Elbow Phase 3




**ELBOW COULEE PHASE 3
COMPLETED IN 2021**



SCHOOL SECTION COULEE PROJECTS



School Section Coulee Phases		
Broken O	Length (miles)	Completed
PHASE 1, Dam Removal, ch re-align	0.3	2021 2022
PHASE 2	1	2023
PHASE 3	1.1	2025
PHASE 4	4.5	2026
Total (miles)	7	



7904 ft

Sun River

School Section Phase 1



BROKEN RANCH

DESIGNED: RLB
DRAWN: RLB
CHECKED: [Signature]
DATE: 08/08/2008

PLAN AND PROFILE VIEW
2 to 1 vertical exaggerated,
PROFILE VIEW

NEW CHANNEL ALIGNMENT, DAM
REMOVAL; SCHOOL SECTION
COULEE, PHASE 1


TETON COUNTY, MONTANA
STA 0+00 through 11+00



SCHOOL SECTION IRRIGATION DAM
REMOVAL LOCATION, LOOKING
DOWNSTREAM AND UPSTREAM,
2022



School Section Phase 2



SCHOOL SECTION PHASE 2
TO BE COMPLETED IN 2023



The background features several sets of curved lines in shades of gray, some solid and some dashed, creating a sense of motion and depth. A prominent blue rectangular box with a white border and a small white triangle at the bottom center contains the main title.

Construction and Monitoring

- GPS Enabled Excavators
- On-Site Materials
- Drone Monitoring
- Fisheries Monitoring



2015

Elbow Coulee Phase 1 NAIP

2021



UAS May 2018



UAS June 2019



2017

Elbow Coulee Phase 2 UAS

2019




0 262.5 525 Feet

UAS May 2018



UAS July 2020





UAS May 2020



UAS July 2021



2020

School Section Coulee Phase 1 UAS

2022



UAS June 2018



UAS July 2023



- Irrigation Dam on School Section Coulee
- Fish passage barrier
- Removed/re-routed October 2021



SCHOOL SECTION ALFALFA
DITCH IRRIGATION DAM
BEFORE AND AFTER





Fisheries Monitoring


Passive Integrated Transponder (PIT) Tag Antenna Array – April 2021



Fisheries Monitoring

PIT Tag Install/Fish Data Processing





Date: 10/8/2023
 Background: 2019 NAIP Imagery
 Projection: NAD83 Montana State Plane 2500

Broken O Ranch

Fish Tracking Telemetry Sites
 Brown Trout CE6D Movement

- Telemetry Sites - Installed April 2021
- Streams
- Sun River







Date: 10/8/2023
 Background: 2019 NAIP Imagery
 Projection: NAD83 Montana State Plane 2500

Broken O Ranch

Whitefish Movement
 Post Dam Removal

- Telemetry Sites - Installed April 2021
- Streams
- Sun River



Conclusions

- Eliminate as many watershed stressors as possible prior to restoration.
- Work closely with the ranch operational management to ensure the projects benefit ranch operations
- Design with fish habitat in mind
- Monitor and adaptively manage



The Broken O Team

- Noah Majerus
- Tanner Tompkins
- Jason Drake
- Robert Sain



Questions

- Accepting applications for 2024